RSK Land & Devlopment Engineering Ltd
18 Frogmore Road, Hemel Hempstead
Hertfordshire, HP3 9RT
Tel: +44 (0) 1442 437500
Fax: +44 (0) 1442 437550

Project Name. :	**WHITTINGTON WAY, PARCEL B**							**BAR BENDING SCHEDULE**						
Project No :	**134215**							Drg No.		**DR-S-1200**		1 OF 1	Rev	**C3**
Schedule Title :	**RC DETAILS GROUND BEAM**							Date Prepared		Drawn		Checked		
	Plots - 268, 279, 296 Garage Plot-286, 275-276							**17.05.2023**		**MKM**		**SSP**		
Member	Bar mark	Type and size	No.of mbrs	No. of bars in each	Total No.	Length of each bar † mm	Shape code	A*	B*	C*	D*	E/R*	Weight	Rev letter
Pargeter	01	H 25	1	2	2	2600	11	300	(2350)				20.020	**C3**
	02	H 10	1	192	192	1675	51	400	350	(130)	(130)		198.427	**C3**
	03	H 16	1	60	60	1925	11	300	(1650)				182.490	**C3**
	04	H 16	1	60	60	1575	11	300	(1300)				149.310	**C3**
	05	H 10	1	192	192	1100	47	350	160	(120)	(120)		130.310	**C3**
	06	H 16	1	12	12	2800	00	2800					53.088	**C3**
	07	H 16	1	16	16	2200	00	2200					55.616	**C3**
	08	H 10	1	20	20	975	51	200	200	(130)	(130)		12.032	**C3**
	09	H 25	1	2	2	3600	11	300	(3350)				27.720	**C3**
	10	H 16	1	36	36	3250	00	3250					184.860	**C3**
	11	H 12	1	10	10	3250	00	3250					28.860	**C3**
	12	H 12	1	18	18	1225	11	125	(1100)				19.580	**C3**
	13	H 12	1	18	18	1900	31	550	150	1100	(150)		30.370	**C3**
	14	H 16	1	24	24	2850	00	2850					108.072	**C3**
	15	H 12	1	20	20	1175	11	125	(1050)				20.868	**C3**
	16	H 16	1	8	8	2650	11	300	(2375)				33.496	**C3**
	17	H 16	1	8	8	2350	11	300	(2075)				29.704	**C3**
	18	H 16	1	12	12	2900	00	2900					54.984	**C3**
	19	H 16	1	4	4	3475	00	3475					21.962	**C3**
	20	H 16	1	4	4	3175	00	3175					20.066	**C3**
	21	H 16	1	16	16	2450	00	2450					61.936	**C3**
	22	H 20	1	4	4	2800	00	2800					27.664	**C3**
	23	H 20	1	4	4	3250	00	3250					32.110	**C3**

This schedule conforms to BS8666-2005

Page Total 1503.55

* Specified in multiples of 5mm

Status: P = Preliminary A = Approval C = Construction

† Specified in multiples of 25 mm

RSK Land & Devlopment Engineering Ltd
18 Frogmore Road, Hemel Hempstead
Hertfordshire, HP3 9RT
Tel: +44 (0) 1442 437500
Fax: +44 (0) 1442 437550

Project Name. :	WHITTINGTON WAY, PARCEL B	BAR BENDING SCHEDULE			
Project No :	134215	Drg No.	DR-S-1200	2 OF 1	Rev C3
Schedule Title :	RC DETAILS GROUND BEAM	Date Prepared	Drawn	Checked	
	Plots - 268, 279, 296 Garage Plot-286, 275-276	17.05.2023	MKM	SSP	

Member	Bar mark	Type and size	No.of mbrs	No. of bars in each	Total No.	Length of each bar † mm	Shape code	A*	B*	C*	D*	E/R*	Weight	Rev letter
Pargeter	24	H 16	1	4	4	5200	00	5200					32.864	C3
	25	H 16	1	4	4	4600	00	4600					29.072	C3
	26	H 16	1	8	8	2325	11	300	(2050)				29.388	C3
	27	H 16	1	4	4	4150	00	4150					26.228	C3
	28	H 25	1	4	4	4150	00	4150					63.910	C3
	29	H 20	1	4	4	2900	00	2900					28.652	C3
	30	H 25	1	2	2	3850	00	3850					29.645	C3
Pargeter Type-1	01	H 25	1	2	2	2600	11	300	(2350)				20.020	
	02	H 10	1	234	234	1675	51	400	350	(130)	(130)		241.833	C3
	03	H 16	1	48	48	1925	11	300	(1650)				145.992	
	04	H 16	1	48	48	1575	11	300	(1300)				119.448	
	05	H 10	1	234	234	1100	47	350	160	(120)	(120)		158.816	C3
	06	H 16	1	14	14	2800	00	2800					61.936	C3
	07	H 16	1	20	20	2200	00	2200					69.520	
	08	H 10	1	20	20	975	51	200	200	(130)	(130)		12.032	
	09	H 25	1	2	2	3600	11	300	(3350)				27.720	
	10	H 16	1	36	36	3250	00	3250					184.860	
	11	H 12	1	10	10	3250	00	3250					28.860	
	12	H 12	1	18	18	1225	11	125	(1100)				19.580	
	13	H 12	1	18	18	1900	31	550	150	1100	(150)		30.370	
	14	H 16	1	24	24	2850	00	2850					108.072	
	15	H 12	1	20	20	1175	11	125	(1050)				20.868	

This schedule conforms to BS8666-2005

Page Total 1489.69

* Specified in multiples of 5mm

Status: P = Preliminary A = Approval C = Construction

† Specified in multiples of 25 mm

RSK Land & Devlopment Engineering Ltd
18 Frogmore Road, Hemel Hempstead
Hertfordshire, HP3 9RT
Tel: +44 (0) 1442 437500
Fax: +44 (0) 1442 437550

Project Name. :	WHITTINGTON WAY, PARCEL B	BAR BENDING SCHEDULE			
Project No :	134215	Drg No.	DR-S-1200	3 OF 1	Rev C3
Schedule Title :	RC DETAILS GROUND BEAM	Date Prepared	Drawn	Checked	
	Plots - 268, 279, 296 Garage Plot-286, 275-276	17.05.2023	MKM	SSP	

Member	Bar mark	Type and size	No.of mbrs	No. of bars in each	Total No.	Length of each bar † mm	Shape code	A*	B*	C*	D*	E/R*	Weight	Rev letter
Pargeter Type-1	18	H 16	1	12	12	2900	00	2900					54.984	
	19	H 16	1	4	4	3475	00	3475					21.962	
	20	H 16	1	4	4	3175	00	3175					20.066	
	21	H 16	1	18	18	2450	00	2450					69.678	C3
	22	H 20	1	8	8	2800	00	2800					55.328	
	23	H 20	1	4	4	3250	00	3250					32.110	
	24	H 16	1	4	4	5200	00	5200					32.864	
	25	H 16	1	4	4	4600	00	4600					29.072	
	26	H 16	1	8	8	2325	11	300	(2050)				29.388	
	27	H 16	1	4	4	4150	00	4150					26.228	
	28	H 25	1	4	4	4150	00	4150					63.910	
	29	H 20	1	4	4	2900	00	2900					28.652	
	30	H 25	1	2	2	3850	00	3850					29.645	
	31	H 16	1	8	8	2425	11	300	(2150)				30.652	
	32	H 16	1	8	8	2725	11	300	(2450)				34.444	
	33	H 16	1	46	46	1675	11	300	(1400)				121.739	C3
	34	H 16	1	36	36	2025	11	300	(1750)				115.182	
	35	H 16	1	16	16	2725	00	2725					68.888	
	36	H 25	1	4	4	5700	00	5700					87.780	
	37	H 16	1	4	4	5700	00	5700					36.024	
	38	H 10	1	49	49	1875	51	500	350	(130)	(130)		56.687	
	39	H 10	1	49	49	1150	47	350	195	(120)	(120)		34.768	
	40	H 16	1	8	8	4050	00	4050					51.192	

This schedule conforms to BS8666-2005

Page Total 1131.24

* Specified in multiples of 5mm

Status: P = Preliminary A = Approval C = Construction

† Specified in multiples of 25 mm

RSK Land & Devlopment Engineering Ltd
18 Frogmore Road, Hemel Hempstead
Hertfordshire, HP3 9RT
Tel: +44 (0) 1442 437500
Fax: +44 (0) 1442 437550

Project Name. :		**WHITTINGTON WAY, PARCEL B**						**BAR BENDING SCHEDULE**						
Project No :		**134215**						Drg No.		**DR-S-1200**		4 OF 1	Rev	**C3**
Schedule Title :		**RC DETAILS GROUND BEAM**						Date Prepared		Drawn		Checked		
		Plots - 268, 279, 296 Garage Plot-286, 275-276						**17.05.2023**		**MKM**		**SSP**		
Member	Bar mark	Type and size	No.of mbrs	No. of bars in each	Total No.	Length of each bar † mm	Shape code	A*	B*	C*	D*	E/R*	Weight	Rev letter
Pargeter Type-1	44	H 16	1	22	22	1650	11	300	(1375)				57.354	**C3**
	45	H 20	1	20	20	1975	11	300	(1725)				97.565	**C3**
	46	H 16	1	2	2	2800	00	2800					8.848	**C3**
	47	H 20	1	8	8	2000	11	300	(1750)				39.520	**C3**
Single Garage	02	H 10	1	66	66	1675	51	400	350	(130)	(130)		68.209	
	03	H 16	1	24	24	1925	11	300	(1650)				72.996	
	04	H 16	1	24	24	1575	11	300	(1300)				59.724	
	05	H 10	1	66	66	1100	47	350	160	(120)	(120)		44.794	
	33	H 16	1	8	8	1675	11	300	(1400)				21.172	
	34	H 16	1	8	8	2025	11	300	(1750)				25.596	
	36	H 25	1	8	8	5700	00	5700					175.560	
	37	H 16	1	8	8	5700	00	5700					72.048	
	42	H 16	1	16	16	2675	00	2675					67.624	
Double Garage	02	H 10	1	125	125	1675	51	400	350	(130)	(130)		129.184	**C3**
	03	H 16	1	29	29	1925	11	300	(1650)				88.204	**C3**
	04	H 16	1	24	24	1575	11	300	(1300)				59.724	
	05	H 10	1	59	59	1100	47	350	160	(120)	(120)		40.043	
	06	H 16	1	8	8	2800	00	2800					35.392	
	07	H 16	1	8	8	2200	00	2200					27.808	
	33	H 16	1	8	8	1675	11	300	(1400)				21.172	
	34	H 16	1	13	13	2025	11	300	(1750)				41.594	

This schedule conforms to BS8666-2005

Page Total 1254.13

* Specified in multiples of 5mm

Status: P = Preliminary A = Approval C = Construction

† Specified in multiples of 25 mm

RSK Land & Devlopment Engineering Ltd
18 Frogmore Road, Hemel Hempstead
Hertfordshire, HP3 9RT
Tel: +44 (0) 1442 437500
Fax: +44 (0) 1442 437550

Project Name. :	WHITTINGTON WAY, PARCEL B							BAR BENDING SCHEDULE						
Project No :	134215							Drg No.		DR-S-1200		5 OF 1	Rev	C3
Schedule Title :	RC DETAILS GROUND BEAM							Date Prepared		Drawn		Checked		
	Plots - 268, 279, 296 Garage Plot-286, 275-276							17.05.2023		MKM		SSP		
Member	Bar mark	Type and size	No.of mbrs	No. of bars in each	Total No.	Length of each bar † mm	Shape code	A*	B*	C*	D*	E/R*	Weight	Rev letter
Double Garage	36	H 25	1	13	13	5700	00	5700					285.285	
	37	H 16	1	13	13	5700	00	5700					117.078	
	41	H 10	1	66	66	1175	47	350	220	(120)	(120)		47.848	
	42	H 16	1	32	32	2675	00	2675					135.248	
	43	H 20	1	10	10	1750	11	300	(1500)				43.225	
	44	H 16	1	12	12	1650	11	300	(1375)				31.284	C3
	45	H 20	1	12	12	1975	11	300	(1725)				58.539	C3

This schedule conforms to BS8666-2005

Page Total 718.51

* Specified in multiples of 5mm

Status: P = Preliminary A = Approval C = Construction

† Specified in multiples of 25 mm