SUBSTRUCTURE MASONRY STRENGTH LEGEND

All Substructure Blockwork to be 7.3N/mm2 Aircrete Blocks, JetFloor Infill blocks to be 3.5N/mm2

Where infill blocks to beam and block floor are built into adjacent walls, the infill block is to be the same strength and density as the wall blockwork.

SUBSTRUCTURE LEGEND

⊕DD1 Direct Drain Connection (No.1). Soil Vent Pipe (No.1)

⊕SVP1

Centre line of drainage outlets to be positioned 75mm from structural Wall

Telescopic Air Vents to ventilate sub floor void, to be positioned at max. 2m c/c. AIR BRICKS NOT TO BE POSITIONED BELOW DOOR THRESHOLD (Door Position Indicated By Dashed Lines).

DOOR THRESHOLD

Thick dashed line denotes ACO 'HEX Drain Brickslot' hidden drainage channel across width of door opening Refer to Engineers and Architects details.

Thin dashed line indicates extent of secondary DPC stepped up to according

Ensure 60mm continuous cavity to substructure

HOUSETYPE COMPLY WITH

APPROVED DOCUMENT M4(1)

Character Area 3 to All Plots

Private Housing - 14, 22, 33, 49, 101 (AS)


- 15, 16, 18, 21, 32, 47, 100 (OPP)

HOUSEPACK TO BE FULLY REVIEWED BY STRUCTURAL ENGINEERS.

Foundations width and depth to be confirmed by Engineers drawings on a site by site basis.

RWP positions to be finalised on Architects drawings on an individual site by site basis.

Meter positions to be finalised on Architects drawings on an individual site by site basis.



NOTES:

All dimensions to be checked on site prior to the commencement of construction and any discrepancy should be reported to the Site Manager.

This drawing may not be reproduced in any part or form without written consent.

All copyrights reserved.

Sub-Contractors MUST ensure that they have the latest issue drawing before they commence

This drawing is to be read in strict conjunction with Housepacks/ Assembly Blocks, all relevant Specifications, schedules and Engineers details.

Rev	Date	Description	Init.
-	29.09.2023	PRELIMINARY ISSUE	PG
Α	01.07.2024	Amended to suit replan.	PG
В	03.07.2024	End extract added.	PG
		Electric meter setting out added.	
С	29.11.2024	Plot numbers amended to suit replan.	KK
D	10.03.2025	Drawing title repositioned.	PAG
		suit floorplan.	
Ε	10.04.2025	Stud partitions to staircase amended to	PAG



Himley Village Bicester Phase 2a

The Bayberry - Timber Frame Substructure Layout (End Plot)

Timber Frame Construction

SCALE	DATE	DRAWN	
1:50 @ A3	Sept 2023	PAG	
DWG NO.		REV.	
BI2a-001-A-	F		

SCALE 1:50