

TRIBRACH ASSOCIATES

Bar schedule ref :

044

04

Rev
letter

Site ref : BLK F-REMEDIAL WORKS

Date prepared : 24-Jul-19

Job no : ERITH PHASE 2 - 218522

Prepared by : BC Checked by : ph

Member	Bar mark	Type and size	No. of mbrs	No. of bars in each	Total no.	Length of each bar † mm	Shape code	A * mm	B * mm	C * mm	D * mm	E/R * mm	Rev letter
BEAM 2	200	H 16	1	2	2	3900	21	150	3650				
	201	H 16	1	8	8	1425	11	150					
	202	H 10	1	20	20	1475	21	550	400				
BEAM 4	203	H 16	1	2	2	2825	11	150					
	204	H 16	1	2	2	1475	11	150					
	205	H 10	1	15	15	1475	21	550	400				
BEAM 8	206	H 16	1	8	8	1425	11	150					
	207	H 16	1	2	2	3225	11	150					
	208	H 16	1	2	2	1325	11	150					
	209	H 10	1	17	17	1475	21	550	400				
BEAM 9	210	H 16	1	10	10	1425	11	150					
	211	H 16	1	2	2	1375	11	150					
	212	H 16	1	2	2	3425	11	150					
	213	H 10	1	18	18	1675	21	600	500				
	214	H 16	1	2	2	1225	11	150					
	215	H 16	1	2	2	2700	00	2700					
	216	H 16	1	2	2	1375	11	150					
	217	H 10	1	15	15	1675	21	600	500				
	218	H 16	1	10	10	1375	11	150					

This schedule conforms to BS 8666:2005

* Specified in multiples of 5mm.

† Specified in multiples of 25mm.

TRIBRACH ASSOCIATES

Bar schedule ref :

045

09

Rev
letter

Site ref : BLK F-REMEDIAL WORKS

Date prepared : 24-Jul-19

Job no : ERITH PHASE 2 - 218522

Prepared by : BC Checked by : ph

Member	Bar mark	Type and size	No. of mbrs	No. of bars in each	Total no.	Length of each bar † mm	Shape code	A * mm	B * mm	C * mm	D * mm	E/R * mm	Rev letter
BEAM 14	219	H 16	1	2	2	6325	11	150					
	220	H 16	1	2	2	1900	00	1900					
	221	H 16	1	2	2	3025	11	150					
	222	H 10	1	44	44	1675	21	600	500				
BEAM 16	223	H 16	1	4	4	1325	11	150					
	224	H 16	1	2	2	3200	00	3200					
	225	H 16	1	2	2	1900	00	1900					
	226	H 16	1	2	2	2700	00	2700					
	227	H 10	1	32	32	1475	21	550	400				
BEAM 18	228	H 10	1	21	21	1675	21	600	500				
	229	H 16	1	2	2	4125	21	150	3875				

This schedule conforms to BS 8666:2005

* Specified in multiples of 5mm.

† Specified in multiples of 25mm.

TRIBRACH ASSOCIATES

Bar schedule ref :

045

10

Rev
letter

Site ref : BLK F-REMEDIAL WORKS

Date prepared : 24-Jul-19

Job no : ERITH PHASE 2 - 218522

Prepared by : BC Checked by : ph

Member	Bar mark	Type and size	No. of mbrs	No. of bars in each	Total no.	Length of each bar † mm	Shape code	A * mm	B * mm	C * mm	D * mm	E/R * mm	Rev letter
BEAM 20	230	H 16	1	2	2	1625	11	150					
	231	H 16	1	2	2	2325	11	150					
BEAM 24	232	H 10	1	1	1	2175	51	500	500				
	233	H 10	1	1	1	775	22	130	500	60			
	234	H 16	1	10	10	1475	11	150					
BEAM 25	235	H 16	1	2	2	1225	11	150					
	236	H 10	1	17	17	1375	21	500	400				
	237	H 16	1	2	2	3325	11	150					
BEAM 30	238	H 16	1	2	2	4225	11	150					
	239	H 10	1	22	22	1675	21	600	500				
	240	H 16	1	2	2	1225	11	150					
BEAM 31	241	H 10	1	18	18	1675	21	600	500				
	242	H 16	1	2	2	1475	11	150					
	243	H 16	1	2	2	5800	00	5800					
	244	H 16	1	2	2	1325	11	150					
	245	H 10	1	30	30	1675	21	600	500				
	246	H 16	1	2	2	3575	21	150	3325				

This schedule conforms to BS 8666:2005

* Specified in multiples of 5mm.

† Specified in multiples of 25mm.

TRIBRACH ASSOCIATES

Bar schedule ref :

045

11

Rev
letterSite ref : BLK F-REMEDIAL WORKSDate prepared : 24-Jul-19Job no : ERITH PHASE 2 - 218522Prepared by : BC Checked by : ph

Member	Bar mark	Type and size	No. of mbrs	No. of bars in each	Total no.	Length of each bar † mm	Shape code	A * mm	B * mm	C * mm	D * mm	E/R * mm	Rev letter
BEAM 32	247	H 16	1	4	4	1325	11	150					
	248	H 10	1	30	30	2275	21	850	600				
	249	H 16	1	4	4	5925	11	150					
BEAMS 34, 42, 43 & 44	250	H 10	4	1	4	1775	51	400	400				
	251	H 16	4	8	32	1125	11	150					
BEAMS 36, 38 to 41 & 46	252	H 16	6	2	12	1325	11	150					
	253	H 10	6	8	48	1575	21	600	400				
	254	H 16	6	2	12	1625	11	150					
BEAMS 45 & 47	255	H 16	2	10	20	1125	11	150					
	256	H 16	2	2	4	1325	11	150					
	257	H 10	2	1	2	1775	51	400	400				
	258	H 10	2	9	18	1575	21	600	400				
	259	H 16	2	2	4	1625	11	150					

This schedule conforms to BS 8666:2005

* Specified in multiples of 5mm.

† Specified in multiples of 25mm.