
DO NOT SCALE DRAWING




Please Note: No allowances have been made on this design for additional loading out of infill blocks or other ancillaries. If this is required, you MUST contact Litecast for loading out advice PRIOR to doing so. Failure to so may result in damage to structural integrity of the floor.



All partitions not supported off a footing below are assumed to be 0.5kN/m² Max. Non-load bearing studding. (Except where indicated on drawing)

Drawing Legend





Closure Block


Thru' vents by builder.


All closure blocks to be bedded. All internal bearing channels must be concrete filled before screed is applied. Shuttering may be required for GT12 and GT18.

Starter Panel - Cut from **FULL PANEL** as indicated on design/section. End Panel - Cut from FULL PANEL or off cut of Starter Panel as indicated on design/section.









Closure Blocks are only included for around the perimeter, as is highlighted on our design. If you would like additional Closure Blocks for internal walls, please contact Litecast.

Section Details shown are auto generated and may not reflect situation on site.

PLEASE NOTE:

Sections should be used to determine panel type for cut rows and all edges are created using full (540mm) panels.

| Ancillaries Schedule | | | |
|----------------------|---------------------------|-------|--|
| Product Code | Description | Count | |
| ANC-GT12F | GT12 540mm Infill Panel | 27 | |
| ANC-GT12MR | GT12 Multi Beam Rail | 6 | |
| ANC-GT122F | GT122 540mm Infill Panel | 42 | |
| ANC-ESCGT12 | GT12 Edge Support Clip | 30 | |
| ANC-PES | Poly Edge Strip | 40 | |
| ANC-LCB | 100mm Large Closure Block | 29 | |
| ANC-AB1 | Air-Brick TERRA | 4 | |
| ANC-UV | Telescopic U/Floor Vent | 4 | |

| Joist Schedule | | | | |
|--------------------------|--------------|--------|-------|--|
| Description | Joist Length | Bay Id | Count | |
| 150mm Floor Joist | 3800 | 1 | 9 | |
| 150mm Floor Joist (Wide) | 5050 | 2 | 10 | |


| Vent flow rates achieved | | |
|--------------------------|--|--|
| 6450 | mm ² Capacity | |
| 2677 | mm²/m P (1500mm²/m MIN) | |
| 541 | mm ² /m ² A (500mm ² /m ² MIN) | |



THERMAL VALUES

PERIMETER/AREA VALUE - 0.202

TARGET U VALUE - 0.12 ACTUAL U VALUE - 0.10



TOTAL LENGTHS AND AREA

150mm - Length 225mm - Length Floor Area 84.700 m 0.000 m 47 m²

DESIGN CRITERIA (WHERE APPLICABLE)

FINISHES - 1.8kN/m² 75mm Steel Fibre/Mesh Reinforced Concrete Screed LIVE LOAD (LL) - Refer To Bay Tag For Loads

OTHER INFILLS - EPS Panel

PARTITIONS - 0.5kN/m² Non Load Bearing Stud PARTITIONS - 3kN/m Non Load Bearing Block

HOUSE TYPE

Harper (Mid)

SITE ADDRESS

Trumps Green Road Virginia Water **GU25 4EU**



DRAWN BY james@litecast.co.uk DATE 02/06/2025

nit 1 Purley Chase Industrial Est. DRG NO.

Tel:-02476 356161 245411-15-GW12