


DO NOT SCALE DRAWING






Installation Guide

Please Note: No allowances have been made on this design for additional loading out of infill blocks or other ancillaries. If this is required, you MUST contact Litecast for loading out advice PRIOR to doing so. Failure to do so may result in damage to structural integrity of the floor.



All partitions not supported off a footing below are assumed to be 0.5kN/m² Max. Non-load bearing studding. (Except where indicated on drawing)



Drawing Legend

- Joist Start Layout Point Poly Start Layout Point
- 150mm Joist 150mm Wide Joist

- Service Hole Position
- Suggested Void Ventilator Position. Those with V graphic have Vertical Ext. Thru' vents by builder.

- Closure Block
- All closure blocks to be bedded. All internal bearing channels must be concrete filled before screed is applied. Shuttering may be required for GT12 and GT18.

- Starter Panel - Cut from FULL PANEL as indicated on design/section.
- End Panel - Cut from FULL PANEL or off cut of Starter Panel as indicated on design/section.

318 150mm Floor Joists with 270mm poly panel between (Poly).

Closure Blocks are only included for around the perimeter, as is highlighted on our design. If you would like additional Closure Blocks for internal walls, please contact Litecast.

Section Details shown are auto generated and may not reflect situation on site.


PLEASE NOTE:
Sections should be used to determine panel type for cut rows and all edges are created using full (540mm) panels.

Ancillaries Schedule		
Product Code	Description	Count
ANC-GT12F	GT12 540mm Infill Panel	22
ANC-GT12H	GT12 270mm Infill Panel	3
ANC-GT122F	GT122 540mm Infill Panel	46
ANC-ESCGT12	GT12 Edge Support Clip	30
ANC-PES	Poly Edge Strip	40
ANC-LCB	100mm Large Closure Block	30
ANC-SCB	100mm Small Closure Block	2
ANC-AB1	Air-Brick TERRA	5
ANC-UV	Telescopic U/Floor Vent	5

Joist Schedule			
Description	Joist Length	Bay Id	Count
150mm Floor Joist (Wide)	5050	1	11
150mm Floor Joist	3400	2	9

Vent flow rates achieved	
6450	mm² Capacity
1654	mm²/m P (1500mm²/m MIN)
676	mm²/m² A (500mm²/m² MIN)

PANELS ON THIS DESIGN ARE



THERMAL VALUES

PERIMETER/AREA VALUE - 0.409

TARGET U VALUE - 0.12 ACTUAL U VALUE - 0.11

a	Revised drawing name and all wall / riser positions	JA	30/05/25
REV	DESCRIPTION	INI	DATE

TOTAL LENGTHS AND AREA		
150mm - Length	225mm - Length	Floor Area
86.150 m	0.000 m	47 m²

DESIGN CRITERIA (WHERE APPLICABLE)

FINISHES - 1.8kN/m² 75mm Steel Fibre/Mesh Reinforced Concrete Screed

LIVE LOAD (LL) - Refer To Bay Tag For Loads

OTHER INFILLS - EPS Panel

PARTITIONS - 0.5kN/m² Non Load Bearing Stud

PARTITIONS - 3kN/m Non Load Bearing Block

HOUSE TYPE

Blommere

SITE ADDRESS

Trumps Green Road

Virginia Water

GU25 4EU

 Unit 1 Purley Chase Industrial Est. Pipers Lane, Nuneston, CV10 0RG Tel : -02476 356161	DRAWN BY james@litecast.co.uk	DATE 30/05/2025
	DRG NO. 245411-7-GW12	REV a