



Project : Fairbridge Way, Burgess Hill

Client : Places for People Homes Ltd

Job No : 100554

By : NNB

Date : 18.03.22

Last revised : 04.10.22

Drg. No

-	0	8	1	5
Sheet No				0
Rev				C02
Status				C

Member	Bar Mark	Type and Size	No of mbrs	No of bars in each	Total No	Length of each bar mm +	Shape Code	A * mm	B * mm	C * mm	D * mm	E/R * mm	Rev Letter
GB1	02	H10	1	54	54	2425	51	640	490	(130)	(130)		C01
	07	H16	1	20	20	3650	11	425	(3250)				C01
	08	H16	1	10	10	5325	46	700	450	3025	45	(700)	C01
GB2	01	H16	1	12	12	1850	11	425	(1450)				C01
	03	H10	1	44	44	1825	51	340	490	(130)	(130)		C01
	05	H16	1	12	12	4175	00						C01
	06	H16	1	6	6	2125	00						
GB3	02	H10	1	44	44	2425	51	640	490	(130)	(130)		C02
	07	H16	1	20	20	3650	11	425	(3250)				C01
	08	H16	1	10	10	5325	46	700	450	3025	45	(700)	C01
GB4	02	H10	1	55	55	2425	51	640	490	(130)	(130)		C02
	08	H16	1	10	10	5325	46	700	450	3025	45	(700)	C01
	09	H16	1	20	20	4175	35	2610	450	700	45	(425)	C01
GB5	03	H10	1	55	55	1825	51	340	490	(130)	(130)		C02
	10	H20	1	8	8	6000	46	850	500	3300	50	(850)	C01
	15	H20	1	16	16	3950	35	2365	500	700	50	(425)	C01
	12	H20	1	5	5	5400	46	850	500	2700	50	(850)	C01
	13	H20	1	5	5	4350	35	2580	500	900	50	(425)	C01

This Schedule conforms to BS 8666:2005

* Specified in multiples of 5mm

+ Specified in multiples of 25mm

Status: P Preliminary

T Tender

C Construction

Bar bending schedule produced by CADS RC 2022.0



Project : Fairbridge Way, Burgess Hill

Client : Places for People Homes Ltd

Job No : 100554

By : NNB

Date : 18.03.22

Last revised : 04.10.22

Drg. No

-	0	8	1	5
Sheet No			0	2
Rev				C02
Status				C

[illegible]

This Schedule conforms to BS 8666:2005

* Specified in multiples of 5mm

+ Specified in multiples of 25mm

Status: P Preliminary

T Tender

C Construction

Bar bending schedule produced by CADS RC 2022.0