



Project : Fairbridge way, Burgess Hill
Client : Places for People Homes Ltd

Job No : 100554
By : NNB
Date : 18.03.22
Last revised : 04.10.22

Drg. No	-	0	8	1	6
Sheet No		0		1	
Rev'n				C02	
Status				C	

Member	Bar Mark	Type and Size	No of mbrs	No of bars in each	Total No	Length of each bar mm +	Shape Code	A * mm	B * mm	C * mm	D * mm	E/R * mm	Rev Letter
GB1	01	H16	1	5	5	5425	00						C01
	02	H16	1	10	10	1850	11	425	(1450)				C01
	03	H10	1	78	78	2425	51	640	490	(130)	(130)		C01
	08	H16	1	5	5	5550	26	700	450	(4400)	45		C01
	09	H16	1	5	5	4225	26	700	450	(3060)	45		C01
	11	H16	1	10	10	3575	11	425	(3175)				C01
	12	H16	1	5	5	5500	26	700	450	(4350)	45		C01
	13	H16	1	5	5	5500	46	700	450	3200	45	(700)	C01
GB2	02	H16	1	12	12	1850	11	425	(1450)				C01
	04	H10	1	67	67	1825	51	340	490	(130)	(130)		C01
	06	H16	1	12	12	4175	00						C01
	07	H16	1	12	12	2125	00						
	10	H16	1	6	6	4300	00						C01
GB3	01	H16	1	5	5	5425	00						C01
	02	H16	1	10	10	1850	11	425	(1450)				C01
	03	H10	1	67	67	2425	51	640	490	(130)	(130)		C02
	08	H16	1	5	5	5550	26	700	450	(4400)	45		C01
	09	H16	1	5	5	4225	26	700	450	(3060)	45		C01
	11	H16	1	10	10	3575	11	425	(3175)				C01
	12	H16	1	5	5	5500	26	700	450	(4350)	45		C01
	13	H16	1	5	5	5500	46	700	450	3200	45	(700)	C01

This Schedule conforms to BS 8666:2005

* Specified in multiples of 5mm

+ Specified in multiples of 25mm

Status: P Preliminary

T Tender

C Construction

Bar bending schedule produced by CADS RC 2022.0



Project : Fairbridge way, Burgess Hill
Client : Places for People Homes Ltd

Job No : 100554
By : NNB
Date : 18.03.22
Last revised : 04.10.22

Drg. No	-	0	8	1	6
Sheet No		0		2	
Rev'n				C02	
Status				C	

Member	Bar Mark	Type and Size	No of mbrs	No of bars in each	Total No	Length of each bar mm +	Shape Code	A * mm	B * mm	C * mm	D * mm	E/R * mm	Rev Letter
GB4	03	H10	1	55	55	2425	51	640	490	(130)	(130)		C02
	14	H16	1	10	10	5600	46	700	450	3295	45	(700)	C01
	15	H16	1	20	20	4025	35	2410	450	750	45	(425)	C01
GB5	04	H10	1	55	55	1825	51	340	490	(130)	(130)		C02
	16	H20	1	5	5	4350	35	2580	500	900	50	(425)	C01
	17	H20	1	16	16	4275	35	2635	500	750	50	(425)	C01
	18	H20	1	8	8	5400	46	850	500	2700	50	(850)	C01
	19	H10	1	5	5	2050	21	725	640	(725)			C01
GB6	04	H10	1	55	55	1825	51	340	490	(130)	(130)		C02
	16	H20	1	5	5	4350	35	2580	500	900	50	(425)	C01
	17	H20	1	16	16	4275	35	2635	500	750	50	(425)	C01
	18	H20	1	8	8	5400	46	850	500	2700	50	(850)	C01
	19	H10	1	5	5	2050	21	725	640	(725)			C01
GB7	03	H10	1	54	54	2425	51	640	490	(130)	(130)		C02
	14	H16	1	10	10	5600	46	700	450	3295	45	(700)	C01
	15	H16	1	20	20	4025	35	2410	450	750	45	(425)	C01
GB3	20	H10	1	12	12	2050	21	725	640	(725)			C02

This Schedule conforms to BS 8666:2005

* Specified in multiples of 5mm

+ Specified in multiples of 25mm

Status: P Preliminary

T Tender

C Construction

Bar bending schedule produced by CADS RC 2022.0



Project : Fairbridge way, Burgess Hill

Client : Places for People Homes Ltd

Job No : 100554

By : NNB

Date : 18.03.22

Last revised : 04.10.22

Drg. No

-	0	8	1	6
Sheet No			0	3
Revn				C02
Status				C

[illegible]

This Schedule conforms to BS 8666:2005

* Specified in multiples of 5mm

Status: P Preliminary

T Tender

C Construction

+ Specified in multiples of 25mm

Bar bending schedule produced by CADS RC 2022.0