



Project : Abbeville Park Burgess Hill

Client : Places for People Ltd

Title : HT34B AS - Plot 263

RC Details of Ground Beams

Job No : 101101

By : MEZ

Date : 04.03.25

Last revised : 19.09.25

Drg. No	-	4	0	0	2
Sheet No	0	1			
Rev	P02				
Status	P				

Member	Bar Mark	Type and Size	No of mbrs	No of bars in each	Total No	Length of each bar mm +	Shape Code	A * mm	B * mm	C * mm	D * mm	E * mm	F * mm	R * mm	Weight (kg)	Rev Letter
PLOT 263	01	B16	1	8	8	8000	00	8000							101.120	
	02	B16	1	39	39	2175	11	350	(1850)						134.024	
	03	B16	1	45	45	1825	11	350	(1500)						129.758	
	04	B16	1	16	16	5350	00	5350							135.248	
	05	B16	1	6	6	3500	35	2350	215	600	35	(350)	215		33.180	
	06	B16	1	6	6	2550	00	2550							24.174	
	07	B8	1	171	171	2100	51	470	495	(115)	(115)				141.844	P02
	08	B8	1	171	171	1500	51	470	200	(115)	(115)				101.318	P02
	09	B8	1	31	31	1800	51	470	345	(115)	(115)				22.041	P02
	10	B8	1	30	30	725	22	115	470	60	(120)				8.591	P02
	11	B16	1	8	8	6275	11	350	(5950)						79.316	P02
	13	B16	1	4	4	6025	11	350	(5700)						38.078	P02
	14	B16	1	4	4	4450	26	900	230	(3300)	35	230			28.124	P02
	15	B16	1	4	4	3625	11	350	(3300)						22.910	P02
	16	B16	1	4	4	7200	26	1250	230	(5700)	35	230			45.504	P02
	17	B16	1	6	6	2450	35	1300	215	600	35	(350)	215		23.226	P02
	18	B16	1	3	3	3150	00	3150							14.931	P02
	19	B16	1	3	3	2450	00	2450							11.613	P02
	20	B16	1	8	8	6300	35	5150	215	600	35	(350)	215		79.632	P02

This Schedule conforms to BS 8666:2020

Page Total 1174.632 kg

* Specified in multiples of 5mm

+ Specified in multiples of 25mm

Status: P Preliminary

T Tender

C Construction