



Project : Fairbridge Way, Burgess Hill

Client : Places for People Homes Ltd

Job No : 100554

By : JLP

Date : 18.03.22

Last revised : 04.10.22

Drg. No

-	0	8	0	1
Sheet No				0
Revn				C02
Status				C

Member	Bar Mark	Type and Size	No of mbrs	No of bars in each	Total No	Length of each bar mm +	Shape Code	A * mm	B * mm	C * mm	D * mm	E/R * mm	Rev Letter
GB1	03	H10	1	53	53	2425	51	640	490	(130)	(130)		C01
	05	H16	1	20	20	3600	11	425	(3200)				C01
	06	H16	1	10	10	5400	46	700	400	3200	40	(700)	C01
GB2	02	H16	1	12	12	1850	11	425	(1450)				C01
	04	H10	1	44	44	1825	51	340	490	(130)	(130)		C01
	10	H16	1	12	12	4175	00						C01
	11	H16	1	6	6	1950	00						C01
GB3	03	H10	1	44	44	2425	51	640	490	(130)	(130)		C02
	05	H16	1	20	20	3600	11	425	(3200)				C01
	06	H16	1	10	10	5400	46	700	400	3200	40	(700)	
GB4	03	H10	1	48	48	2425	51	640	490	(130)	(130)		C02
	08	H16	1	10	10	5050	46	700	400	2850	40	(700)	C01
	09	H16	1	20	20	3550	35	2100	400	650	40	(425)	C01
GB5	04	H10	1	46	46	1825	51	340	490	(130)	(130)		C02
	16	H20	1	4	4	5325	46	850	500	2625	50	(850)	C01
	07	H25	1	4	4	5725	46	1050	600	2425	60	(1050)	C01
	12	H25	1	8	8	3525	35	1900	600	650	60	(425)	C01
	15	H20	1	8	8	3525	35	2000	500	650	50	(425)	C01

This Schedule conforms to BS 8666:2005

* Specified in multiples of 5mm

+ Specified in multiples of 25mm

Status: P Preliminary

T Tender

C Construction

Bar bending schedule produced by CADS RC 2022.0



Last revised : 04.10.22

-	0	8	0	1
Sheet No			0	2
Revn				C02
Status				C

Bar bending schedule produced by CADS RC 2022.0