

|                                        |              |               |                               |
|----------------------------------------|--------------|---------------|-------------------------------|
| <b>CALA HOMES (THAMES)<br/>LIMITED</b> |              | Status:       | <b>CONSTRUCTION</b>           |
|                                        |              | Drawing No:   | <b>SA00394-4408-S-HT3-BBS</b> |
|                                        |              | Sheet No:     | <b>1</b>                      |
| Job No:                                | <b>48174</b> | Revision:     | <b>E</b>                      |
| Prepared By:                           | <b>DR</b>    | Date:         | <b>01-09-2023</b>             |
| Checked By:                            | <b>OH</b>    | Last revised: | <b>23/10/23</b>               |

[illegible]

This schedule conforms to BS 8666:2020

\* Specified in multiples of 5mm

+ Specified in multiples of 25mm

Total weight on this page [kg] = 1159.284

Status:

P Preliminary

T Tender

### C Construction

|                                    |              |               |                               |
|------------------------------------|--------------|---------------|-------------------------------|
| <b>CALA HOMES (THAMES) LIMITED</b> |              | Status:       | <b>CONSTRUCTION</b>           |
|                                    |              | Drawing No:   | <b>SA00394-4408-S-HT3-BBS</b> |
|                                    |              | Sheet No:     | <b>2</b>                      |
| Job No:                            | <b>48174</b> | Revision:     | <b>D</b>                      |
| Prepared By:                       | <b>DR</b>    | Date:         | <b>01-09-2023</b>             |
| Checked By:                        | <b>OH</b>    | Last revised: | <b>23/10/23</b>               |

|           |                                                                               |
|-----------|-------------------------------------------------------------------------------|
| Section:  | <b>BROOKLANDS COLLEGE WEYBRIDGE</b>                                           |
| Location: | <b>HT3 Piled Foundation Bar Bending Schedule<br/>PLOTS: 208 (h) &amp; 216</b> |

| Summary of bar lengths and weights |                                               |             |
|------------------------------------|-----------------------------------------------|-------------|
| Bar Size                           | Total length(m)<br>(of all bars in this size) | Weight (kg) |
| 10                                 | 371.375                                       | 229.1       |
| 16                                 | 588.700                                       | 930.1       |

|                  |             |
|------------------|-------------|
| Total Weight[kg] | 1.159tonnes |
|------------------|-------------|

Additional Information :