PRELIMINARY
SUBJECT TO SECTION 38 APPROVAL

THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT DESIGN DRAWINGS AND OTHER INFORMATION.

© 2023 RPS Group

Notes

1. This drawing has been prepared in accordance with the scope of RPS's appointment with its client and is subject to the terms and conditions of that appointment. RPS accepts no liability for any use of this document other than by its client and only for the purposes for which it was prepared and provided.
2. If received electronically it is the recipients responsibility to print to correct scale. Only written dimensions should be used.
3. This drawing should be read in conjunction with all other relevant drawings and specifications.

For guidance only. Do not scale off this drawing

1:20 - 0	200mm	400mm	600mm	800mm	1000	1200	1400	1600	1800	2000
1:100 - 0	1m	2m	3m	4m	5m	6m	7m	8m	9m	10m
1:50 - 0	1m	2m	3m	4m	5m					
1:5 - 0	100mm	200mm	300mm	400mm	500mm					

Adoptable Kerbing Key

- HB2 Kerb - 125mm upstand
- BN Kerb 255 x 125mm - 3-4mm upstand
- BN Kerb 255 x 125mm - 25mm upstand
- BN Kerb 255 x 125mm - 50mm upstand
- EBN Kerb 50 x 150mm - Laid Flush
- Transition Kerb
- Raised Table Transition Kerb
- Tactile Paving
- Bollard

Refer to drawing 104-01 for construction details

Adoptable Surfacing Key

- Footway Construction
- Residential Road Construction (blacktop)
- Block Paving Construction
- Vehicle Crossover Construction
- Ramp Location
- Shared Private Drive Construction (blacktop)
- Private Drive Construction (blacktop)
- Shared Private Drive Block Paving Construction
- Private Drive Block Paving Construction
- POS Path Construction
- Grasscrete Construction - to be installed as per manufacturers guidance

Refer to drawing 104-01 for construction details

Temporary Sales car parking to be returned to landscaping on completion of development.

Future development access. To be constructed on Miller instruction. Ground worker to provide allowance.

Warehouse
Stone
Factory
El Sub Sta
Care Home
Shelter
Barleycroft
Garage
Track
B 197
Wickfield

Rev	Description	By	Chd	Date
P04	Ramps to raised tables updated to suit road construction details	KK		23.02.26
P03	Site entrance radii has changed from 7.5m to 6m, kerbing updated to suit	KK		19.02.26
P02	Updated to suit latest layout & client comments	KK		03.11.25
P01	First issue	GD	KK	12.08.25

rps MAKING COMPLEX EASY
A TETRA TECH COMPANY
4th Floor, 1 Newhall Street, Birmingham, West Midlands B3 3NH
T: +44 121 622 8020 E: rpswlv@rpsgroup.com

Client: Miller Homes

Project: London Road, Woolmer Green

Title: Kerbing and Surfacing

RPS Project Number	Scale @ A0	Date Created
794-DES-CAS-31468	NTS	22.07.2025

Task Team Manager	Information Author	Task Information Manager
KKelsall	GD	KKelsall

Status: S4

Document Number: 31468-RPS-xx-xx-DR-C-103-01

Revision: P04

Project Code - Originator - Functional - Spatial - Type - Discipline - Number

rpsgroup.com

I:\31468\Drawings\Civils\31468-RPS-xx-xx-DR-C-103-01-Adoptable Kerbing and Surfacing.dwg